



2022 Traditional Series Log Home Materials List



Miscellaneous Materials Supplied Per Plan

- **Basement Stairs:** 2 x 12 stringers and treads with 1" pine risers
- **Loft Stairs:** 2 x 12 stringers, SYP (Southern Yellow Pine) treads with 1" pine risers
- **Porch Posts:** 6 x 6 spruce or pine
- **Hardware for Pilaster Studs**
- **Interior Railing:** 4 x 4 posts, 2 x 4 rails, vertical slats. Note--Railing provided for loft areas and 1st to 2nd floor staircase
- **Exterior Framed Walls:** 2 x 6 Partition frame, 7/16" OSB, log siding
- **House Sill Tie Downs:** from banding
- **Construction Documents: 2 Sets**
- **Construction Guide**

Optional Material that can be added to the Traditional Series package

- **Exterior Pressure Treated Railings:** 2 x 2, 2 x 4 and 5/4 PTSYP
- **Basement Railings:** 4 x 4 posts, 2 x 4 rails, vertical slats
- **Interior Partition Framing:** 2 x 4 or 2 x 6 shoe, double plate, studs (24" O.C. as standard unless otherwise instructed to design to 16" O.C.), blocking, headers and fillers as necessary.
- **Interior Partition Sheathing:** 1" knotty pine v-match boards—See "Add" on price sheet for upgrade cost on standard models
- **Flat Ceiling Sheathing:** 1" knotty pine v-match boards—See price sheet for upgrade cost on standard models
- **Interior Doors:** Solid pine raised panel interior doors with hardware and locksets per plan
- **Beam Ceiling:** (replaces standard ceiling joists) 4 x 8 spruce ceiling joists, joist hangers as required w/ 2" v-match flooring for loft

- **Exterior Door Upgrade:** Therma-Tru Classic Craft, pre-hung & weatherstripped
- **Log Siding Corner Projections:** At skirt or dormer area
- **Solid Log Wall at flat truss rafter gables**
- **Andersen Window Products:** Optional HeatLock glazing

Log Siding Garage Materials

- **Sills:** 2x4: PTSYP
- **Wall Framing:** 24" O.C. with window and door headers as required
- **Wall Sheathing:** 7/16" OSB (Oriented Strand Board)
- **Log Siding:** Milled shiplap log siding for walls and gables, Eastern White Pine, kiln dried
- **Roof Framing:** Pre-built truss rafters with ladder and fly rafter material and hardware. NOTE: We do not supply temporary or permanent bracing.
- **Roof Sheathing:** 5/8" AdvanTech®
- **Fascia and soffit materials**
- **Service Door:** Therma-Tru® Smooth Star® fiberglass door system
- **Andersen® 400 Series Windows:** Low-E4 glass Tilt-Wash double-hung with screens

NOTE-Always refer to your individual price quote and Signed Order Form for specific material supplied with your home design.

*NOTE: The 'by others' materials note is for informational clarity and general reference. It is not meant to be an exhaustive list. See note above.